

***Underground Utilities and Systems Experience***

**OWNER/CLIENT:**

Charlotte Mecklenburg Utilities  
5100 Brookshire Blvd.  
Charlotte, NC 28216

**PROJECT SUMMARY:**

- DHGI Prime Contractor
- Installed 5,078 LF of 54" Pipe & 8,722 LF of 48" Pipe
- Installed 49 Manholes and (2) - 84" tunnels
- Multiple creek crossings

**PROJECT COMPLETED:**

03/2005—03/2007

**Long Creek Parallel Outfall  
Charlotte, NC**



Long Creek Parallel Outfall Contract A was a project that DHGI received through a competitive hard bid process for the Charlotte Mecklenburg Utility Division. The work entailed the installation of 13,800 linear feet of 48" and 54" reinforced concrete sewer pipe and 49 manholes in a gravity application. Two 84" tunnels and multiple creek crossings were installed during the construction of this project. Several tie ins requiring 24 hour bypass pumping applications occurred to make this project active in phases. The contract finished on time and within budget at just over \$7,000,000.